

CHANGE ORDER

PROJECT: CC 1-10 Road Bond Paving
Invitation for Bid # 17-0-2024/GB

CHANGE ORDER: 1 **DATED:** 07/22/24

CONTRACTOR: Timothy Rose Contracting
ADDRESS: 1360 Old Dixie Hwy SW
Vero Beach, FL 32962

JUSTIFICATION:
 Due to inconsistencies in the road depth, a change in the work type is required to meet standards to the road base with addition of curb requirements and removal of existing debris. Requirements include, pre-mill high areas and leave the 8-inch base, 77 LF of 3' Valley Gutter R&R, and MOT. This will meet ADA requirement for the sidewalks and safety concerns.

CONTRACT PRICE AND TIME IMPACT:

ORIGINAL AWARDED CONTRACT AMOUNT:	\$8,894,381.30
CURRENT CONTRACT AMOUNT:	\$8,894,381.30
INCREASE/DECREASE IN CONTRACT AMOUNT:	\$423,377.00
NEW CONTRACT AMOUNT:	\$9,317,758.30
CURRENT CONTRACT <u>FINAL</u> COMPLETION DATE:	12/03/24
INCREASE/DECREASE IN CONTRACT TIME: (DAYS)	0
NEW CONTRACT COMPLETION DATE:	12/03/24

REQUESTING DEPARTMENT'S CONCURRENCE AND APPROVAL:

 Department Head

 Date

ORDERED BY THE CITY OF PALM BAY

ACCEPTED BY THE CONTRACTOR

 City Manager/Chief Procurement Officer

 Printed Name & Title

 Date

 Signature

 Date

CC 1-10 Road Bond Paving

#	Item No.	Description	Qty	Unit	Unit Price	Value
1		MAINTENANCE OF TRAFFIC (1.5" Paving)	1.00	LS	\$ 4,750.00	\$4,750.00
2		MAINTENANCE OF TRAFFIC (1.5" Mill Operation)	1.00	LS	\$ 4,750.00	\$4,750.00
3		MAINTENANCE OF TRAFFIC (Detour at Valley Gutter)	1.00	LS	\$ 2,465.00	\$2,465.00
4		3' VALLEY GUTTER R&R	77.00	LF	\$ 122.00	\$9,394.00
5		DEMO EXISTING BULL NOSE	1.00	LS	\$ 2,350.00	\$2,350.00
6		TYPE "D" CURB	36.00	LF	\$ 62.00	\$2,232.00
7		MILL 1"-2" OF ASPHALT (Trucking included)	10.00	DY	\$ 8,758.60	\$87,586.00
8	327-70-6	MILLING EXIST ASPH PAVT, 1.5" AVG DEPTH	40,000.00	SY	\$ 3.25	\$130,000.00
9	334-1-13	SUPERPAVE ASPHALT CONCRETE, TRAFFIC C (1" SP-9.5)	(2,300.00)	TN	\$ 180.50	-\$415,150.00
10	334-1-13	SUPERPAVE ASPHALTIC CONCRETE, TRAFFIC C (1.5" SP-9.5)	3,500.00	TN	\$ 170.00	\$595,000.00
Sub Total						\$423,377.00

Total						\$423,377.00
--------------	--	--	--	--	--	---------------------

Approved by:

 Public Works Project Manager