

Purchase Order No.: 241830

PR No.: 81441

Bid # 24-0-2024/SZ

**CHANGE ORDER****PROJECT:** 24GO10 - Minton Rd Road Bond PavingInvitation for Bid # 24-0-2024/SZ**CHANGE ORDER:** 1**DATED:** 08/26/24**CONTRACTOR:** Ranger Construction Industries, Inc**ADDRESS:** 4510 Glades Cutoff Rd.  
Ft. Pierce, FL 34981**JUSTIFICATION:**

Pricing for addt'l striping requested by the City. Addt'l MOT needed. Overrun for Portland Cement due to material proctor. New sidewalk installation, omitted in original bid. Pricing for overruns on contract items. Items including addt'l concrete removal required. Milling SY increase. Addt'l curb installation to match plans. Loop assembly not accounted for in SQ.

**CONTRACT PRICE AND TIME IMPACT:**

ORIGINAL AWARDED CONTRACT AMOUNT:	\$1,222,539.55
CURRENT CONTRACT AMOUNT:	\$1,222,539.55
INCREASE/DECREASE IN CONTRACT AMOUNT:	\$85,991.30
NEW CONTRACT AMOUNT:	<b>\$1,308,530.85</b>
CURRENT CONTRACT <u>FINAL</u> COMPLETION DATE:	12/14/24
INCREASE/DECREASE IN CONTRACT TIME: (DAYS)	0
NEW CONTRACT COMPLETION DATE:	12/14/24

**REQUESTING DEPARTMENT'S CONCURRENCE AND APPROVAL:**\_\_\_\_\_  
Department Head\_\_\_\_\_  
Date**ORDERED BY THE CITY OF PALM BAY****ACCEPTED BY THE CONTRACTOR**\_\_\_\_\_  
City Manager/Chief Procurement Officer\_\_\_\_\_  
Printed Name & Title\_\_\_\_\_  
Date\_\_\_\_\_  
Signature\_\_\_\_\_  
Date

24GO10 - Minton Rd Road Bond Paving

Purchase Order No.: 241830

PR No.: 81441

Bid # 24-O-2024/SZ

24GO10 - Minton Rd Road Bond Paving

#	Item No.	Description	Qty	Unit	Unit Price	Value
1		CEMENT - CEMENT TREATED BASE (2%)	86.00	TONS	\$ 252.10	<b>\$21,680.60</b>
2	110-4-10	REMOVAL OF EXISTING CONCRETE	36.00	SY	\$ 68.60	<b>\$2,469.60</b>
3	327-70-5	MILLING EXISTING ASPHALT PVT, 2" AVE DEPTH	1,604.00	SY	\$ 11.30	<b>\$18,125.20</b>
4	520-1-10	WITH TRANSITION (24" WIDE), TYPE F	81.00	LF	\$ 279.40	<b>\$22,631.40</b>
5	660-210-6	LOOP ASSEMBLY, F&I, TYPE F	1.00	EA	\$ 3,240.00	<b>\$3,240.00</b>
6	522-1	CONCRETE SIDEWALK AND DRIVEWAYS 4" THICK	39.00	SY	\$ 425.50	<b>\$16,594.50</b>
7		STRIPING CHANGES ADDING SKIP STRIPES ACCROSS MALABAR	1.00	LS	\$ 1,250.00	<b>\$1,250.00</b>
8						<b>\$0.00</b>
9						<b>\$0.00</b>
10						<b>\$0.00</b>
<b>Sub Total</b>						<b>\$85,991.30</b>

<b>Total</b>						<b>\$85,991.30</b>
--------------	--	--	--	--	--	--------------------

Approved by:

 9/3/24  
Public Works Project Manager



Submitted To: John T. McCall  
Project Manager/Sr. Engineering Inspector  
City of Palm Bay  
Public Works  
John.McCall@palmbayflorida.org

Ranger Construction Industries  
1200 Elbow Way  
Winter Garden, FL 34787  
(407) 856-9255

### Change Order Request #1

ITEM	Pay Item Code	DESCRIPTION	Base Rate	QUANTITY	UOM	Total Cost
	522-1	Concrete Sidewalk and Driveways 4" Thick	\$ 425.50	39 SY		\$ 16,594.50
		Cement-Cement Treated Base	\$ 252.10	86 TN		\$ 21,680.60
		Striping Changes adding skip stripes across Malabar	\$ 1,250.00	1 LS		\$ 1,250.00

Estimated Total: \$ 39,525.10

Notes:

- Unit pricing for Concrete Sidewalk from 24GO11 Waco Road Paving. Takeoff is attached
- Cement-Cement Treated Base quantity adjusted to include 16.5 lbs/SY Portland Cement to concur with the 1.6% Mix Design and quantity represents the estimated overrun
- Striping Changes will be nominal for quantities, CO request to accommodate additional maintenance of traffic crossing Malabar Rd

 9/3/24



Submitted To: John T. McCall  
Project Manager/Sr. Engineering Inspector  
City of Palm Bay  
Public Works  
John.McCall@palmabayflorida.org

Ranger Construction Industries  
1200 Elbow Way  
Winter Garden, FL 34787  
(407) 656-9255

## Change Order Request #2

ITEM	Pay Item Code	DESCRIPTION	Base Rate	QUANTITY	UOM	Total Cost
	110-4-10	Removal of Existing Concrete	\$ 68.60	36 SY		\$ 2,469.60
	327-70-5	Milling Existing Asphalt Pvmnt, 2" Avg Depth	\$ 11.30	1604 SY		\$ 18,125.20
	520-1-10	Type F Curb with Transitions	\$ 279.40	81 LF		\$ 22,631.40
	660-210-6	Loop Assembly, F&I, Type F	\$ 3,240.00	1 Ea		\$ 3,240.00
Estimated Total:						\$ 45,466.20

Notes:

- Unit pricing for all overruns at contract unit price
- Removal for existing concrete quantity not captured in original SQ
- Milling SY increased with the substitution of FDR SY decrease at Malabar intersection and Jupiter Intersection
- Curbing footage to include extended island on Jupiter
- Traffic Loop count to include left turn lane from Jupiter EB to Minton NB

 9/3/24